List of Materials

Materials	*Quantity*	*Purpose*
Foundation		
Cement pier blocks	4	foundation blocks
Adjustable galvanized pier block brackets	4	connection between block and beam
4" X 4" X 10' lumber	2	foundation beams
Floor		
2" X 6" X 12' kiln dried lumber	8	floor framing
Nail strips for nail gun (10d)—smooth shank	≈ 2 lbs. (or 1 box)	hardware—framing
Tyvek moisture fabric	≈ 60 sq. ft.	attached underneath floor panels
4' lath strip	22 per Hut, or a bundle	holds on Tyvek & used on wall braces
18 gauge, ¼" X 1" galvanized staples	1 box	hardware—wall panelling
R-19 fiberglass insulation	≈ 60 sq. ft.	insulation—floor
¾" X 4' X 8' plywood (one sanded side preferred)	2	flooring
Floor paint	1 gallon	floor paint
Deck		
2" X 6" X 14' kiln dried lumber	4	for deck surface
All-in-one wood stain & sealer (cedar tone)	1 gallon	sealant—deck, wall braces, trim, interior walls
2" X 4" X 12' lumber	2	deck joists and deck legs
Walls		
R-13 fiberglass insulation	≈ 65 sq. ft.	insulation—wall
2" X 4" X 12' kiln dried lumber	10	wall framing
½" X 4' X 8' plywood (one sanded side preferred)	2	exterior walls
¼" X 4' X 8' plywood (one sanded side preferred)	2	interior walls