Step 5I: Fasteners should go in every other space along the wall braces.

Step 5J: Also fasten the brackets along the top edge of both walls with screws into the wall blocks, which are located by finding the heads of the screws holding them to the plywood interior sheathing. Put a bracket at every block.

Figure 5K: This is a closeup detailing the orientation of the fourth cattle panel (the half panel). Notice that the cut end is positioned next to the third panel and not at the front of the Hut.

Figure 5L: Now you have all of your roof structure in place and you can start adding insulation to it.