

Figure 6E: A view from outside the Hut looking at the installed foam insulation. Notice how snug the panel is to the cattle panel! **Step 6F:** Attach the outer reflective insulation over the entire *interior* space (which is 10' in length from the outside of the back wall to the outside of the front wall). Throw the roll of insulation over the Hut, attach it with T-50 staples on one bottom end, pull it tight and fasten it to the other bottom edge with more T-50 staples. *Make sure to pull it taut before fastening.*

Step 6G: We also staple the exterior insulation to the blocks along the wall-ends to squeeze it into the wall and reduce the gap between the insulation and the wall.

STEP 6H: Ready to move onto the next step!

